

PROJEK NO : PR/DCC-SP-01

PROJEK TITLE : RENOVATION WORK FOR CSC OFFICE SIPITANG

BIL	DESCRIPTION	UNIT	QUANTITY	TOTAL (MYR)	
				RATE	AMOUNT
1.0	SITE PREPARATION AND DEMOLITION WORKS				
	1.1 To demolish entire existing facilities it shall include as follow: 5 unit rollershutter and all debris must be clear away in daily basis.	LS	1		
	1.2 Providing Construction waste bin and clearing of site after completion and making good directed by client.	LS	1		
	1.3 Report - Digital photographs and soft copies showing work progress before, during and after completion of work.	LS	1		
	1.4 Supply all safety equipment such as PPE full set / safety harness / workers and so on to carry out the work.	LS	1		
2.0	FLOOR FINISHES				
	<u>INTERNAL FLOOR FINISHES</u>				
	2.1 Supply and construct cement screeding average 30mm to 40 mm thickness to the interior floor area. All surface must be leveled and ready for laminated flooring and tile finish.				
	2.1.1 Manager Office - 10'(L) x 10'(W)	Sqft	100.00		
	2.1.2 General Office	Sqft	711.75		
	2.1.3 Server Room - 4.1' (L) x 8.23' (W)	Sqft	33.74		
	2.1.4 Strong Room	Sqft	238.73		
	2.1.5 Pantry	Sqft	224.42		
	2.2 Supply and install Laminated SPC Flooring Finishes 8mm to the following area:				
	2.2.1 Manager Office - 10'(L) x 10'(W)	Sqft	100.00		
	2.2.2 General Office	Sqft	711.75		
	2.2.3 Server Room - 4.1' (L) x 8.23' (W)	Sqft	33.74		

[illegible]

	5.2.4 Strong Room Door (Fire Door) with BOMBA Certificate and 2H Size: 3' (W) x 8' (H) 5.3 Supply and install single leaf Stainless Steel Framed 10mm thk tempered clear glass door With sand blasted strips, 1.2mm Bronze tinted Mirror finish stainless steel frames 50 x 110mm. Come with floor hinges, lock pad and handle bars to client approval. 5.3.1 Manager Room Size : 3' (W) x 8'(H) 5.4 Supply and install Stainless Steel Grill on the 5.4.1 Outside back door 5.4.2 Inside toilet window ROLLER SHUTTER 5.5 Supply and install automatic roller shutter completed with all necessary connection and fittings 5.5.1 Size : 9.67' (W) x 9.83' (H) - Front	No No No No No	1 1 1 1 1		
6.0	SANITARY FITTING				
	SINK – PANTRY AREA Supply and install item below including inlet and outlet system plumbing work. 6.1 Stainless steels sink 1.47' (W) x 2.62' (L) X 2.62' (H) with frame steels 6.2 Stainless steel flexible kitchen water tap and Pipe line use G.I 25mm	LS No	1 1		
7.0	COMPLETION PERIOD		MONTH	WEEK	DAY
	7. 1 Time frame for completion of work for CSC Sipitang Office				
GRAND TOTAL					

NOTE:

- PLEASE ATTACH THE PRICE RATE WITH 1 COPY VIA BQ AND 1 COPY OF THE PRICE RATE FOLLOWED BY THE COMPANY NAME.
- PLEASE COPY THE COMPANY NAME PROVIDED ON THE RIGHT AND SIGNATURE.
- PLEASE ATTACH THE COMPANY PROFILE (WORK EXPERIENCE, COMPANY BANK ACCOUNT STATEMENT, ORGANIZATION CHART, CIDB, PUKONSA AND RELATED) AND PLACE IN AN ENVELOPE WITH THE PRICE (SEALED ENVELOPE).
- THESE UPGRADING WORKS ARE GIVEN A TIME PERIOD OF 3 WEEKS TO BE COMPLETED.
- PLEASE LABEL THE PROJECT TITLE AND PROJECT NUMBER (PR/HQ-05) ON THE ENVELOPE.
- BY SIGNING THIS DOCUMENT, I/WE CONFIRM THAT ALL PERSONAL AND COMPANY INFORMATION PROVIDED IS TRUE, ACCURATE, AND COMPLETE. I/WE HEREBY CONSENT TO SABAH CREDIT CORPORATION COLLECTING, RECORDING, STORING, USING, PROCESSING, AND, IF NECESSARY, DISCLOSING SUCH INFORMATION TO RELEVANT PARTIES FOR THE PURPOSES OF MANAGEMENT, EVALUATION, QUOTATION PROCESSING, PROCUREMENT, CONTRACT ADMINISTRATION, COMPLIANCE WITH LEGAL REQUIREMENTS, AND ANY OTHER PURPOSES RELATED TO THIS QUOTATION EXERCISE.
- I/WE UNDERSTAND THAT THE PROCESSING OF THIS PERSONAL DATA IS SUBJECT TO THE PROVISIONS OF THE PERSONAL DATA PROTECTION ACT 2010 (ACT 709) AND THAT SABAH CREDIT CORPORATION WILL TAKE REASONABLE MEASURES TO PROTECT THE CONFIDENTIALITY AND SECURITY OF THE DATA PROVIDED, IN ACCORDANCE WITH APPLICABLE LAWS.

(COMPANY NAME & SIGNATURE)