

Project No : PR/HQ-05

Project Title : Proposed Installation of Mezzanines Flooring at IT Department, 3rd Floor, Wisma PPS, Pekan Baru Donggongan, 89500 Penampang Sabah.

BIL	WORK DESCRIPTION	UNIT	QUANTITY	TOTAL	
				RATE	RM
1	PRELIMINARIES & SITE WORKS				
1.1	Provide temporary canvas/plastic hoarding to protect existing office furniture, flooring, and equipment from dust/sparks during hot works.	LS	1		
1.2	Providing Construction waste bin and clearing of site after completion	LS	1		
1.3	Supply all safety equipment such as PPE full set / safety harness / workers and so on to carry out the work.	LS	1		
2	STRUCTURAL STEEL WORK (SUPPORT STRUCTURE)				
2.1	Install primary support columns and framing using Rectangular Hollow Section (RHS) tube size 2" x 4" x 2.3mm thick, cut to length to maintain a clearance height of 8.9 ft from floor level, inclusive of base plates size 8"x 10", anchor bolts, and welding.	no	45		
2.2	Install secondary floor joists/purlins spaced at appropriate centers using Rectangular Hollow Section (RHS) tube size 2" x 3" x 3.0mm thick and Rectangular Hollow Section (RHS) tube size 2" x 3" x 2.3mm thick , welded securely to primary frames.	sqft	890.91		
2.3	Apply 1 coat of zinc chromate anti-rust primer and 2 coats of gloss finish paint to all new rectangular steel tube structures.	LS	1		

2.4	Install heavy duty hook with wire rope steel to support the mezzanine floor	No	9		
2.5	Install L-shape mounting bracket at the corner mezzanine edges near wall.	No	17		
3.0	MEZZANINE FLOORING				
3.1	Install 4.5mm thick MS Chequered Plates (Size: 4' x 8') over the steel joists. Plates to be perimeter-welded, ground smooth at joints, and securely anchored to cover a total area.	sqft	890.91		
3.2	Apply anti-slip protective paint over the chequered plate floor area.	LS	1		
4.0	STAIRCASE & SAFETY EDGING				
4.1	Fabricate and install steel structural staircase using Rectangular Hollow Section (RHS) tube size 2" x 3" x 3.0mm thick for stringers, and chequered plate cuts for stair treads to reach the 2712.72mm high platform with handrail. Size : 1385.62 mm (W) x 1606.3mm (L) x 2712.72mm (H)	LS	1		
4.2	Install perimeter handrail and balustrade (1,000mm height) along exposed mezzanine edges using 2" x 2"	LS	1		
TOTAL					

NOTE:

- Please attach the price rate with 1 copy via BQ and 1 copy of the price rate followed by the company's letterhead.
- Please state the company name provided on the right and signature.
- Please attach the Company Profile (Work Experience, Company Bank Account Statement- the latest 3 Months, Organization Chart, Trading License, Pukonsa and related) and place in an envelope with the price (sealed envelope).
- These upgrading works are given a time period of 3 weeks to be completed.
- Please label the Project Title and Project Number (PR/HQ-05) on the envelope.
- By signing this document, I/We confirm that all personal and company information provided is true, accurate, and complete. I/We hereby consent to Sabah Credit Corporation collecting, recording, storing, using, processing, and, if necessary, disclosing such information to relevant parties for the purposes of management, evaluation, quotation processing, procurement, contract administration, compliance with legal requirements, and any other purposes related to this quotation exercise.
- I/We understand that the processing of this personal data is subject to the provisions of the personal Data Protection Act 2010 (act 709) and that Sabah Credit Corporation will take reasonable measures to protect the confidentiality and security of the data provided, in accordance with applicable laws.

(COMPANY NAME & SIGNATURE)